



6" COMPOUND METER MAJOR COMPONENTS			
PART	DESC	LAY LENGTH	COMM. CODE
A	6" X 4" FLG TEE	16"	047-34-6456
B	6" FLG GATE VALVE	10 $\frac{1}{2}"$	048-22-9706
C	6" FLG STRAINER	9"	066-81-7431
D	6" COMPOUND MTR (NEPTUNE TRU/FLO)	24"	066-81-1627
E	2" SCREW TAP	N/A	048-20-4304
F	NOMINAL 48"W X 72"L MTR VAULT	SEE CDD-LP-215	056-25-4415
J	2" LINE VALVE WITH LOCK RING	N/A	048-20-4804
K	SERVICE LOCK	N/A	053-43-2465

NOTES:

- CUSTOMERS REQUESTING NEW SERVICE INSTALLATIONS SHALL NOT INSTALL CUSTOMER PORTION OF LATERAL ("HOUSE PIPE") PRIOR TO SPJUC PORTION OF LATERAL AND METER ASSEMBLY BEING INSTALLED.



San Francisco  
**Water  
Power  
Sewer**

Services of the San Francisco Public Utilities Commission

WATER ENTERPRISE - CITY DISTRIBUTION DIVISION STANDARD PLANS

**WATER SERVICES**  
**6-INCH COMPOUND METER ASSEMBLY**  
**(STANDARD INSTALLATION)**

DATE	3/7/2017	REV.	DRAWING NO.	SHEET
SCALE	N.T.S.	1	CDD-LP-203F	64