


SEE SHEET
CDD-LP-202B FOR
CONTINUATION TO TAP
AT WATER MAIN

A PLAN VIEW OF 2" POINT OF CONNECTION AT METER
N.T.S.

END SFPUC SERVICE LATERAL WITH METER
FLANGE FOR DOMESTIC SERVICES, FOR
COMBINATION AND FIRE SERVICES, SEE NOTES
1, 2 AND 3 AND SECTION VIEW



MIN 6" BAND OF CONCRETE AROUND
PERIMETER OF BOX
INSTALL PER BOX MANUFACTURER
REQUIREMENTS

INSTALL
PLUMBING BY
CUSTOMER

SEE SHEET
CDD-LP-202B FOR
CONTINUATION TO TAP
AT WATER MAIN

SEE NOTE 1

B SECTION VIEW OF 2" POINT OF CONNECTION AT METER
N.T.S.

NOTES:

1. FOR LONG SERVICE LATERALS ONLY (MAIN ON FAR SIDE OF STREET WITH RESPECT TO CUSTOMER), INSTALL BURIED LINE VALVE JUST OUTSIDE OF LIP OF GUTTER.
2. FOR 2-INCH COMBINATION DOMESTIC/FIRE SERVICES, A CHECK VALVE IS INSTALLED DOWNSTREAM OF THE WATER METER.

3. CUSTOMER FLANGE SHALL NOT BE INSTALLED UNTIL AFTER CITY LATERAL IS INSTALLED UP TO CITY FLANGE.

4. CUSTOMERS REQUIRING METER SET INSTALLATIONS SHALL LEAVE ENOUGH EXCAVATED SPACE IN SIDEWALK AREA TO ALLOW FOR MEASUREMENT OF METER SET ASSEMBLY AND TO PLACE THE METER ASSEMBLY IN THE GROUND WITH APPROPRIATELY-SIZED METER BOX.

SUPERSEDES A-1240-2B



San Francisco
**Water
Power
Sewer**

Services of the San Francisco Public Utilities Commission

WATER ENTERPRISE - CITY DISTRIBUTION DIVISION STANDARD PLANS

WATER SERVICES
2-INCH SERVICE LATERAL CONNECTION AT METER
(DOMESTIC AND COMBINATION SERVICE)

DATE	10/1/2016	REV.	DRAWING NO.	SHEET
SCALE	N.T.S.	0	CDD-LP-202C	52