



4" COMPOUND METER MAJOR COMPONENTS			
PART	DESC	LAY LENGTH	COMM. CODE
A	4" FLG TEE	13"	047-34-6440
B	4" FLG GATE VALVE	9"	048-22-9704
C	4" STRAINER	7-0 $\frac{1}{2}$ "	066-81-7430
D	4" COMPOUND MTR (NEPTUNE TRU/FLO)	20"	066-81-1617
E	2" SCREW TAP	N/A	048-20-4304
F	NOMINAL 36"W X 60"L MTR VAULT	SEE CDD-LP-214	056-25-4410
I	2" LINE VALVE WITH LOCK RING	N/A	048-20-4804
J	SERVICE LOCK	N/A	053-43-2465

NOTES:  
1. CUSTOMERS REQUESTING NEW SERVICE INSTALLATIONS SHALL NOT INSTALL CUSTOMER PORTION OF LATERAL ("HOUSE PIPE") PRIOR TO SFJUC PORTION OF LATERAL AND METER ASSEMBLY BEING INSTALLED.



San Francisco  
**Water  
Power  
Sewer**

Services of the San Francisco Public Utilities Commission

WATER ENTERPRISE - CITY DISTRIBUTION DIVISION STANDARD PLANS

## WATER SERVICES 4-INCH COMPOUND METER ASSEMBLY (STANDARD INSTALLATION)

DATE 3/7/2017

REV.

DRAWING NO.

SHEET

SCALE N.T.S.

1

CDD-LP-203E

62