



6" COMPOUND METER MAJOR COMPONENTS (WITH SPOOL PIECE)			
PART	DESC	LAY LENGTH	COMM. CODE
A	6" X 4" FLG TEE	16"	047-34-6456
B	6" FLG GATE VALVE	10 1/2"	048-22-9706
C	6" FLG STRAINER	9"	066-81-7431
D	6" COMPOUND MTR (NEPTUNE TRU/FLO)	24"	066-81-1627
E	2" SCREW TAP	N/A	048-20-4034
F	NOMINAL 48"W X 96"L MTR VAULT	SEE CDD-LP-216	056-25-4420
G	6" SPOOL PIECE ASSEMBLY	2'-9 3/8"	NO CODE
H	6" VICTAULIC COUPLING TYPE 31	N/A	NO CODE
I	2" LINE VALVE WITH LOCK RING	N/A	048-20-4804
J	SERVICE LOCK	N/A	053-43-2465

- NOTES:
- CUSTOMERS REQUESTING NEW SERVICE INSTALLATIONS SHALL NOT INSTALL CUSTOMER PORTION OF LATERAL ("HOUSE PIPE") PRIOR TO SFPUC PORTION OF LATERAL AND METER ASSEMBLY BEING INSTALLED.
  - LATERAL SHALL BE STUBBED OUT 4 FT BEHIND CURB W/2" BLOW OFF FOR FLUSHING AND DISINFECTION.
  - USE 1/4" THICK BLIND GASKET ON EITHER SIDE OF SPOOL PIECE. USE 3/8" THICK GASKET IN ALL OTHER LOCATIONS

THIS DRAWING SHALL ONLY BE USED IN CASES WHERE A WATER SERVICE LATERAL IS BEING INSTALLED WITH A METER VAULT PRIOR TO A WATER "METER SET." THIS CONDITION REQUIRES PRE-APPROVAL FROM SFPUC-CDD ENGINEERING DIVISION AND THE SPOOL PIECE ASSEMBLY SHALL BE FURNISHED AND INSTALLED BY CDD STAFF.



San Francisco  
**Water  
Power  
Sewer**

Services of the San Francisco Public Utilities Commission

WATER ENTERPRISE - CITY DISTRIBUTION DIVISION STANDARD PLANS

## WATER SERVICES

### 6-INCH COMPOUND SPOOL PIECE ASSEMBLY

DATE	3/7/2017	REV.	1	DRAWING NO.	CDD-LP-203F-SP	SHEET	65
SCALE	N.T.S.						