


SEE SHEET  
CDD-LP-202B FOR  
CONTINUATION TO TAP  
AT WATER MAIN

END SFPUC SERVICE LATERAL WITH METER  
FLANGE FOR DOMESTIC SERVICES, FOR  
COMBINATION AND FIRE SERVICES, SEE NOTES  
1, 2 AND 3 AND SECTION VIEW




MIN 6" BAND OF CONCRETE AROUND  
PERIMETER OF BOX  
INSTALL PER BOX MANUFACTURER  
REQUIREMENTS

**A** PLAN VIEW OF 2" POINT OF CONNECTION AT METER  
N.T.S.

SEE SHEET  
CDD-LP-202B FOR  
CONTINUATION TO TAP  
AT WATER MAIN

2"  
THREADED  
ANSI/AMSE  
16.5 150#  
COMPANION  
FLANGE.  
SEE NOTE  
3



**B** SECTION VIEW OF 2" POINT OF CONNECTION AT METER  
N.T.S.

NOTES:

1. FOR 2-INCH COMBINATION  
DOMESTIC/FIRE SERVICES, A CHECK VALVE  
IS INSTALLED DOWNSTREAM OF THE WATER  
METER.
2. CUSTOMER FLANGE SHALL NOT BE  
INSTALLED UNTIL AFTER CITY LATERAL IS  
INSTALLED UP TO CITY FLANGE.

3. CUSTOMERS REQUIRING METER SET  
INSTALLATIONS SHALL LEAVE ENOUGH  
EXCAVATED SPACE IN SIDEWALK AREA TO  
ALLOW FOR MEASUREMENT OF METER SET  
ASSEMBLY AND TO PLACE THE METER  
ASSEMBLY IN THE GROUND WITH  
APPROPRIATELY-SIZED METER BOX.



San Francisco  
**Water  
Power  
Sewer**

Services of the San Francisco Public Utilities Commission

WATER ENTERPRISE - CITY DISTRIBUTION DIVISION STANDARD PLANS

**WATER SERVICES**  
**2-INCH PEXA SERVICE LATERAL CONNECTION AT  
METER (DOMESTIC AND COMBINATION SERVICE)**

DATE	01/17/2020	REV.	DRAWING NO.	SHEET
SCALE	N.T.S.		CDD-LP-202G	56